

GRID LOCATION	BOTTOM ELEVATION
2/E	74'-5"7/16

TOTAL QTY.	UNIT QTY.	DIAMETER	TYPE	LENGTH	SITE / WORKSHOP
4		3/4"	A325N_TC	2 1/2"	Site

BILL OF MATERIAL								
QTY	ASSEMBLY MARK	PIECE MARK	TYPE	SIZE	LENGTH	WEIGHT	FINISH	GRADE
	5C2			COLUMN				
1			I	W8X67	18'-3 1/2"	1226.3		A992
2		5a5		L4X4X3/8	0'-5 3/4"	9.3		A36
2		6p3		FL3/4"X8 1/2"	1'-4"	57.9		A36
4		6p22		PL3/4"X3 13/16"	0'-7 1/8"	22.9		A36
1		7p1		FL3/4"X8 1/2"	1'-4"	28.9		A36
Tie anchors	1	7p2		PL3/4"X12 1/2"	2'-1 1/2"	61.0		A36
	2	7p21		PL3/4"X3 13/16"	0'-7 1/8"	11.4		A36
	2	SHOP BOLTS		3/4"Ø A325N_TC BOLT	0'-2 1/2"			
	TOTAL					1417.7		

Tie-plates structures

ONE - COLUMN - 5C2

